भारतीय कपास निगम लिमिटेड

The Cotton Corporation of India Limited

(भारत सरकार का उपक्रम(वस्त्र मंत्रालय के अंतर्गत् ,

निगमित पहचान संख्या :U51490MH1970GOI14733

सी सी आय बेयर हाऊसिंग कॉम्प्लेक्स ,5 एस.प्लाट नं,सेक्टर –के डब्लू सी) 410218 -नवी मुंबई ,कलंबोली ,महाराष्ट्र राज्य(

दूरभाष्/PHONE/फैक्स/FAX:022-27420436/27424191 बेब साईट/website : www.cotcorp.org.in

ई/मेल-E-mail:kalamboli@cotcorp.com

प्रशासकीय एवं पंजीकृत कार्यालयकपास भवन प्लॉट नं.3:ए सेक्टर -,10सीबीडी बेलापुर(महाराष्ट्र राज्य)400614 – नवी मुंबई ,

दूरभाष् /PHONE:27579217 ∘ग्राम/GRAM:COTCORPIND ∘फैक्स/FAX:(022)27576030-9219-6069

ई/मेल-E-mail:headoffice@cotcorp.com वस्त्र् मंत्रालय बेब साईट /Ministry of Textiles website : www.ministryoftextiles.gov.in

CCI/KLMB/Firefighting/2019-20 Date: 05.03.2020

Re-TENDER NOTICE

The Cotton Corporation of India Ltd. invites sealed tenders in two bids system from experienced Contractors/ Firms/ Companies for Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218

Sr. No.	Particulars of the work	Blank Tender document Cost in Rs.	E. M. D in Rs.	Completion period from the date of Issuance of Work Order/ Award of work
1.	Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218	NIL	15,000/-	21 days

1. Blank tender forms for the said work are available at above address free of cost, **on all working days between 11.00 am to 5.00 p.m. before tender opening date.**

2. The tender documents can also be down loaded from the corporation web site i.e. www.cotcorp.org.in and Government Tender Portal www.eprocure.gov.in.

3. Earnest money amounting to Rs. 15,000/- in the form of Crossed Demand Draft/Pay Order/Banker's Cheque drawn on any of the nationalized/ commercial Scheduled Banks drawn in favour of THE COTTON CORPORATION OF INDIA LTD., must accompany each tender. Any Tender not accompanied by the requisite Earnest Money and other documents that are not complete, is liable to be rejected.

4. The pre bid meeting will be held at CCI Warehousing Complex ,Plot S-5, Sector -KWC, Kalamboli, Navi Mumbai - 410 218(Maharashtra State) on 11.03.2020 at 04:00 pm.

5. Tenderer should submit the tender as under:
Envelope A– (Technical Bid-I with all enclosures and EMD)
Envelope B - (Financial Bid-II),
Envelope C: Envelope "C" should contain both Envelope "A" & Envelope "B"
Each envelope must be super scribed as "**Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218.**" and should bear the full address of tenderer at left side bottom.

6. The sealed tenders must be submitted /dropped in the **Tender Box placed at the office premises of the Corporation at** at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218 upto 3:00 PM on 17.03.2020.

7. Technical Bids of the tenders submitted and Financial Bids of the tenderers who are found technically qualified shall be opened on the same day i.e. **on 17.03.2020 at 3.30 p.m. in the presence of tenderers who may wish to remain present.**

THE CORPORATION RESERVES THE RIGHT TO ACCEPT OR REJECT ANY TENDER(s) WITHOUT ASSIGNING ANY REASON THEREOF. HOWEVER, PARTY MAY SEEK THE REASONS OF THE SAME FROM THE CORPORATION.

Dy. GENERAL MANAGER

भारतीय कपास निगम लिमिटेड

The Cotton Corporation of India Limited

(भारत सरकार का उपक्रम(वस्त्र् मंत्रालय के अंतर्गत् ,

निगमित पह्चान संख्या :U51490MH1970GOI14733

सी सी आय वेयर हाऊसिंग कॉम्प्लेक्स ,5 एस.प्लाट नं,सेक्टर –के डब्लू सी) 410218 -नवी मुंबई ,कलंबोली ,महाराष्ट्र राज्य(

दूरभाष्/PHONE/फैक्स/FAX:022-27420436/27424191 बेब साईट/website : www.cotcorp.org.in

ई/मेल-E-mail:kalamboli@cotcorp.com

प्रशासकीय एवं पंजीकृत कार्यालयकपास भवन प्लॉट नं.3:ए सेक्टर -,10सीबीडी बेलापुर(महाराष्ट्र राज्य)400614 – नवी मुंबई ,

दूरभाष् /PHONE:27579217 ०ग्राम/GRAM:COTCORPIND ०फैक्स/FAX:(022)27576030-9219-6069

ई/मेल-E-mail:headoffice@cotcorp.com वस्त्र् मंत्रालय बेब साईट /Ministry of Textiles website : www.ministryoftextiles.gov.in

TENDER DOCUMENT FOR

Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218

TECHNICAL BID- I

INDEX

Sr.No.	Particulars	Page No.
1	Check list for self-attested documents	1
2	Submission of tender and Declaration	2 -3
3	Scope of work and Terms and Conditions of the Tender	4-8
4	Technical Bid Submission Form	9

CHECK LIST OF SELF ATTESTED DOCUMENTS

Please make tick (√) Mark

1. a, Blank tender document obtained from office	Yes	No
b. Tender document down loaded from web site	Yes	No
2. Earnest Money Deposit Amount of Rs. 15,000/- in favour of The Cotton Corporation of India Ltd., payable at Mumbai is enclosed.	Yes	No
3. Registration of various authorities and their Nos. for Eligibility Criteria *(Self attested Copies of the same shall be enclosed)*		
a. Permanent Account Numer	Yes	No
(Self-attested Copies of the same shall be enclosed)		
b. GST No.	Yes	No
(Self-attested Copies of the same shall be enclosed)		
c. Valid Electrical contractor license number	Yes	No
(Self-attested Copies of the same shall be enclosed)		
d. Valid License to act as Licensed agency for the purpose of Fire Prevention and Life safety measures issued by Maharashtra Agnishaman Seva Sanchalanalaya, Government of Maharashtra *(Self-attested Copies of the same shall be enclosed)*	Yes	No
4. The intending Tenderer must have in its name as prime contractor experience of having successfully completed similar nature of works in any Office Building of Government/PSU/Private organizations of repute during last Five years, should be either of the following: **a. Three similar completed works costing not less than the amount of equal to Rs. 4.00 Lakhs each** **OR** **b. Two similar completed works costing not less than the amount of equal to Rs. 5.00 Lakhs each** **OR** **c. One similar completed works costing not less than the amount of equal to Rs. 8.00Lakhs.**	Yes	No
(Self-attested Copies of completion certificates/work orders issued by the concerned departments/firms/agency, shall be enclosed)		

Signature and seal of Tenderer
Name
Capacity /authority to sign
Full address:

Date: _____

To,
The Cotton Corporation of India Ltd.,
"CCI Warehousing Complex "
Plot No. S-5 , Sector –KWC,
Kalamboli ,
Navi Mumbai- 410218

Sub: Re-Tender for repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218

Dear Sir,

1 I/We have read and understood all the terms & conditions of the tender and other instructions and hereby undertake to abide by them. I/ We also undertake that we have not been blacklisted / barred by any Government / quasi Government/ Public Undertaking,

2 I/We are enclosing herewith, Demand Draft/ Pay Order No. _____ dt. _____ in your favour, towards earnest money deposit of **Rs. 15,000/-.**

3 I/We have filled and signed each page of the tender documents and the same are enclosed here with.

4 I/We hereby submit our Technical Bid along with necessary annexure i.e. Annexure –I(Scope of Work), Annexure-II(General Terms and Conditions) and Annexure III(Technical Bid Submission Form).

5. I/ We shall make available to the Corporation any additional information it may find necessary or require to supplement or authenticate the Technical Bid.

6. I/ We acknowledge that the Corporation shall be relying on the information provided in the Technical Bid for selection of the entity for undertaking the aforesaid Scope of Work, and I/ we certify that all information provided herein is true and correct; nothing has been omitted which renders such information misleading; and all documents accompanying the Technical Bid are original copies or true copies thereof.

7. This statement is made for the express purpose of my/ our selection for the award of the aforesaid Scope of Work as mentioned in the Tender document.

8. I/ We understand that you may cancel the Tender Process at any time and that you are neither bound to accept any Bid that you may receive nor to invite the Bidders to Bid for the Scope of Work, without incurring any liability to the Bidders.

9. I/ We hereby irrevocably waive any right or remedy which I/ we may have at any stage at law or howsoever otherwise arising to challenge or question any decision taken by the Corporation in connection with the selection of the Bidder, or in connection with the Tender Process itself, in respect of the above mentioned Scope of Work and the terms and implementation thereof.

10. I/ We have studied all the Tender Documents carefully. I/ We understand that, except to the extent as expressly set forth in the Tender Form, I/ we shall have no claim, right or title arising out of any documents or information provided to me/ us by the Corporation or in respect of any matter arising out of or relating to the Tendering Process including the award of the Scope of Work.

11. I/ We acknowledge the right of the Corporation to reject my/ our Technical Bid without assigning any reason or otherwise and hereby waive, to the fullest extent permitted by applicable law, my/ our right to challenge the same on any account whatsoever.

12. I/ We agree and undertake to abide by all the terms and conditions of the Tender Form document.

13. In witness thereof, I/ we submit this Technical Bid under and in accordance with the terms of the Tender Form document. I/We also hereby declare that tender documents have been downloaded from CCI website www.cotcorp.org.in or www.eprocure.gov.in and it is submitted in original without any alterations/modifications/deletions/additions.

Yours Faithfully.

Signature and seal of tenderer

Name

Capacity /authority to sign

Full address:

Annexure-I to the Technical Bid
(SCOPE OF WORK)

1. The scope of work is as under

Sr. No.	Description	Qty.	Units
1	Refurbishing and revisioning of Main Electrical sprinkler system Motor Kirloskar make 65HP (Pump Room No. 1) with Motor driven pump Kirloskar make model no. DB 100/26 on replacing of Pump Gland Pusher, sleeve, rewinding, Painting of motor and pump, Gasket set, Supporting stand shaft, Gland rope, Terminal connection box, Bearing set DE/NDE on motor and pump, motor REWINDING, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	Set
2	Refurbishing and revisioning of Jocky Electrical sprinkler system Motor Kirloskar make 15HP (Pump Room No. 1) with Motor driven pump Kirloskar make model no. CPHM 25/26 on replacing of Pump Gland Pusher, rewinding, Painting of motor and pump, sleeve, Gasket set, Supporting stand shaft, Gland rope, Terminal connection box, Bearing set DE/NDE on motor and pump, motor REWINDING, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	Set
3	Refurbishing and revisioning of DIESEL DRIVEN PUMP Kirloskar make model no. DB 100/40 (Pump Room No. 1) on replacing of Pump Gland Pusher, sleeve, Gasket set, Gland rope, Terminal connection box, Bearing set DE/NDE, Painting of pump, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	No.
4	Refurbishing and revisioning of DIESEL Engine Kirloskar make model no. RB-66 (Pump Room No. 1) on replacing of Engine spares oil 20 Ltr, oil filter element, Fuel filter kit 1.1 ltr, sleeve for nozzle holder, nozzle leak off pipe, leak off pipe connecter, Fuel pipe plastic braided, hose connecting water outlet, worm drive hose clips-2, hose 38x54, worm drive hose clips -10, Hose, Hose clips 32x48, Hose clips 28x30, Flexible cables, set of joints and rubber o ring set, set of copper washers set, V-belt, set of joints RB 66 and diaphragm, repairing and service of starter and Alternator with servicing charges etc. complete as required.	1	No.
5	Supply of new 12 Volts, 1800 MHD Exide make battery with 150 Sq. mm. copper single core cable with copper lugs etc. Complete as required.	6	No.
6	Modification of starter panel in pump room no. 1 of Main Electrical sprinkler system Motor 65HP, Jocky Electrical sprinkler system Motor 15 HP and battery charging panel on Diesel engine set RB-66 on replacing of 0-500Volt voltmeters, RYB indication lamps, on/off/trip indication lamps, on/off push buttons, all control functions including automatic starting of engine and trickle charging of batteries, over load relay, reset chord push button, control fuse, HC fuses with servicing charges etc. complete as required.	1	Set
7	Refurbishing and revisioning of Jocky Electrical sprinkler system Motor Crompton Greaves make 15KW/20HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. DB 32/26 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, water deflector, Coupling L150 with servicing charges etc. complete as required.	1	Set
8	Refurbishing and revisioning of Main Electrical sprinkler system Motor Crompton Greaves make 90KW/120HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. 6UP4 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	Set

9	Refurbishing and revisioning of DIESEL Engine Greaves Ltd make model no. 4-YDC/126 BHP (Pump Room No. 2) on replacing of Engine spares Greaves maxtherm 15w40 oil 50 Ltr, oil filter element, Fuel filter kit 1.1 ltr, Fuel Micro filter kit 1.1Ltr, Instakool coolant 5 ltrs 2 pack, set of hoses, set of hose clamps, cleaning of diesel fuel tank, diesel fuel tank level gauge, Fuel Flexible GK-056 pipe 3 ft, Fuel Flexible GK-019 pipe 3 ft, Banjo bolts set, copper washer set, repairing and service of starter and Alternator with servicing charges etc. complete as required.	2	Nos.
10	Refurbishing and revisioning of DIESEL DRIVEN sprinkler PUMP Kirloskar make model no. CPHM 125/40 with 70KC2-100HP (Pump Room No. 2) on replacing of Pump Gland Pusher, Shaft sleeve, Gasket set, Gland rope, Bearing set DE/NDE, Painting of pump, key set, coupling rubber star with servicing charges etc. complete as required.	1	No.
11	Refurbishing and revisioning of DIESEL DRIVEN Hydrant PUMP Kirloskar make model no. 6UP4 (Pump Room No. 2) on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	No.
12	Refurbishing and revisioning of Main Electrical Hydrant system Motor Crompton Greaves make 75KW/100HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. 6UP4 on replaceing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, cooling pipe, Key set, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	Set
13	Refurbishing and revisioning of Jocky Electrical Hydrant system Motor Crompton Greaves make 15KW/20HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. DB 32/26 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Key set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling L150 with servicing charges etc. complete as required.	1	No.
14	Servicing and reconditioning of MCCB control panel in pump room no. 2 and DIESEL Engine Greaves Ltd make on replacing of 0-500Volt voltmeters, control fuse link, NS type connectors, Indication lamps, on/off/trip indication lamps, on/off push buttons, Heater, contactor, all control functions including automatic starting of engine and trickle charging of batteries, over load relay, with servicing charges etc. complete as required.	1	Set
15	Refurbishing and revisioning of valve inside connected on sprinkler and Hydrant line in pump room no. 1 & 2	1	Lot
16	Supply of new 80 mm CI Foot Valve Kirloskar make with installation complete as required.	2	No.
17	Supply of new 200 mm CI Foot Valve Kirloskar make with installation complete as required.	4	No.

Sr. No.	Make Of Components is as under:	Make
1	Diesel Engine 4 YDC -126 BHP Spare(Pump Room No. 2)	Greaves Ltd.
2	Diesel Engine RB_66 -90 BHP Spare(Pump Room No. 1)	Kirloskar Ltd.
3	Battary 12 Volts 1800 MHD (Pump Room No. 1 & 2)	Exide Ltd.
4	Main Motor Sprinkler 65 HP Spare (Pump Room No. 1)	Kirloskar Ltd.
5	Jocky Motor Sprinkler 15 HP Spare(Pump Room No. 1)	Kirloskar Ltd.
6	Motor Driven Pump DB 100/26 Spare (Pump Room No. 1)	Kirloskar Ltd.
7	Motor Driven Pump 25/26 spare (Pump Room No. 1)	Kirloskar Ltd.
8	Diesel Driven Pump DB 100/40 spare (Pump Room No. 1)	Kirloskar Ltd.
9	0-500 Volts Voltmeter (Analog)	AE
10	Indication Lamp	TEKNIC
11	Push Button	TEKNIC
12	Over Load Relay	TEKNIC

13	Control Fuse	GE
14	HRC Fuses	BUSSMANN
15	Main Motor Sprinkler 120 HP Spare (Pump Room No. 2)	Crompton Greaves
16	Jocky Motor Sprinkler 20 HP Spare(Pump Room No. 2)	Crompton Greaves
17	Diesel Driven Pump CPHM 125/40 spare (Pump Room No. 2)	Kirloskar Ltd.
18	Diesel Driven Pump 6UP4 spare (Pump Room No. 2)	Kirloskar Ltd.
19	Motor Driven Pump DB 32/26 Spare (Pump Room No. 2)	Kirloskar Ltd.
20	Main Motor Hydrant 100 HP Spare (Pump Room No. 2)	Crompton Greaves
21	Jocky Motor Hydrant 20 HP Spare(Pump Room No. 2)	Crompton Greaves
22	80 MM CI Foot Valve	Kirloskar Ltd.
23	200 MM CI Foot Valve	Kirloskar Ltd.
24	Bearings	DE/NDE

2. The above scope of work includes furnishing of all materials, equipment, labour, scaffolding company applicator, transport, tools etc complete.

3. The quantum of work involved is given in the bill of quantities, however it shall be clearly understood that the quantities are only approximate and meant for the purpose of tender comparison only and no claim whatsoever, will be entertained by the OWNER if the actual quantities of work differ from those indicated in the schedule or if any items of work are deleted from the schedule either partly or wholly, nor shall any claim be put forward by the contractor on grounds of overheads and or loss of anticipated profit etc.

4. The item rates quoted in the bill of quantity should also remain valid for a 25% (Quantum of work) Plus or minus variation in the quantity of work awarded and plus or minus 10% of total contracted value.

5. The work should be carried as per approved scope of work listed in the Bill of Quantity". Should there be any circumstances warranting change in the scope of work, then same should be effected only after prior written approval of the Competent Authority.

6. The work shall have to be completed as per the tender terms under the supervision of Officials of the Corporation.

Annexure-II to the Technical Bid (General Terms and Conditions) :

1. Party/ tenderer shall visit the site before submitting its bids to ascertain the site conditions, nature of work and location, to avoid any confusion.

2. The offer shall remain valid for a period of 60 days from the last date of opening of tenders.

3. Evaluation of technical Bid-I shall be as per elegibility criteria and finacial Bid-II of the tenderer shall be opened only if it qualifies the technical Bid-I . The Corporation reserves it right not to consider the Tender of any party if the performance of the party is not satisfactory in past.

4. Earnest Money deposit amounting to Rs. 15,000/-(Rupees Fifteen thousand only)in the form of Crossed Demand Draft/Pay Order drawn on any Nationaliesd / commeriacial scheduled banks in favour of the cotton corporation of india ltd., payable at Mumbaimust be accompany the technical Bid-I.

5. Persons/firms/body corporate registered with National Small Scale Industries Corporation or State Small Scale Industries, Corporation are exempted from payment of Earnest Money Deposit subject to the production of proof of valid current registration certificate along with the tender.

6. The sucessful tenderer shall have to make payment of 10% value of the work order towards secuirity deposit out of which 50% of the sceurity depsoit after reduction of EMD of Rs. 15,000/- shall be made within 5 working days from the date of work order and balance 50% shall be deducted from the Bill of the tenderer, which shall be kept as security deposit as mentioned in clause no. 16. The same shall be refunded after the completion of defect liability period / warranty period of 24 months. In addition to this the successful Bidder shall also have to submit the Performance Bank Guarantee equivalent to the tender award value (i.e. Contract Value) for the period equivalent to defect liability period of 24 months otherwise the payment for the work completed as per the work order may not be released by the Corporation.

7. If the tenderer neglects or refuses for their rates quoted after submission of their tender to comply with the above conditions or any of them, the earnest money deposit already paid shall be forfeited. This is applicable in case of the party surrenders it self himself from their rates quoted and not ready to execute even if fit for award of work by the corporation or back out from the work by keeping it incomplete. In such case the party may also be blacklisted by the Corporation.

8. All the rates quoted should be inclusive of all material, labour, transportation, scaffolding etc. complete except applicable Taxes.

9. Complete work as per technical specifications should be completed within 21 days from the date of issuance of work order. If work is not completed within stipulated period then penalty @ rate of 0.5 % will be imposed on per week basis delay subject to a maximum of 5% of total amount of the work order.

10. No escalation clause shall be considered for any rise in material, labour or other inputs etc. etc. Similarly, no extra unit rate shall be considered in case of increase or decrease in quantity of individual items. The party shall have to complete the same within the accepted rates.

11. The electricity and water will be given free of cost to the contractor from the available source. In case it is not available then the contractor shall have to make their own arrangement for the same to avoid the delay in completion of work.

12. The corporation shall release payment of work in one single bill including full and final bill after the satisfactory completion of work and submission of bill.

13. The work will be executed as per the work order and as per the directions of the official In-Charge.

14. Extension of time for completion of work shall not be granted except for natural calamities and other unseen reasons. However, the contractor shall take proper approval from the OfficialIn Charge in writing.

15. For any damage or injury to any third party or labour is the sole responsibility of the contractor and the Corporation is not responsible for any payment of compensation. The contractor is fully responsible of all such risks and compensation in accordance with all Act & rules for the said works.

16. The defect liability for the total work will be 24 months from the date of completion of works as certified by the Official in Charge.

17. In case of any dispute or difference arising out of or in relation to this work, same shall be governed by The Arbitration & Conciliation Act 1996. An Arbitrator (other than an employee of the Corporation) shall be appointed by the Competent Authority of The Cotton Corporation of India Ltd., whose decision shall be final and binding upon the parties.

18. The legal jurisdiction for the purposes of this sale shall always be at Navi Mumbai.

Signature and seal of tenderer

Name

Capacity /authority to sign

Full address:

1. Name of the firms:	M/s. _____ Official Address: _____ _____ City: -_____ PIN: - _____ Tel.No. _____ (O)__ _____(R) Mobile No. _____ Email. _____
1a. Blank tender documents had from office	YES NO
1b. Blank tender document down loaded from CCI's web site.	YES NO
2. Earnest Money Deposit AmountRs. 15,000/-& their details:	Rs. _____ (Rupees _____) Drawn on _____ Vide DD/PO No. _____ In favour of The Cotton Corporation of India Ltd., Mumbai is enclosed.
3. A. Permanent Account Number *(Self attested Copies of the same shall be enclosed)* **B. GST No.** *(Self attested Copies of the same shall be enclosed)* **C. Valid Electrical Contractor License issued by state/ central Government/bodies** *(Self attested Copies of the same shall be enclosed)* ***D.* Valid License to act as Licensed agency for the purpose of Fire Prevention and Life safety measures issued by Maharashtra Agnishaman Seva Sanchalanalaya, Government of Maharashtra** *(Self-attested Copies of the same shall be enclosed)*	**A. PAN No.** _____ **B. GST No.** _____ **C. Electrical Contractor License No.** _____. **Valid up to (DD_MM_Y)** __.____._____ **D.**
4. The intending Tenderer must have in its name as prime contractor experience of having successfully completed similar nature of works in any Office Building of Government/PSU/Private organizations of repute during last Five years, should be either of the following: a. Three similar completed works costing not less than the amount of equal to Rs. 4.00 Lakhs each OR b. Two similar completed works costing not less than the amount of equal to Rs. 5.00 Lakhs each OR c. One similar completed works costing not less than the amount of equal to Rs. 8.00 Lakhs	**I.** a. Name of the Agency: _____ b. Address of Work & Location :_____ c. Date of award of work: _____ d. Value of Work done: Rs._____ e. Date of completion: _____ **II.** a. Name of the Agency: _____ b. Address of Work & Location :_____ c. Date of award of work: _____ d. Value of Work done: Rs._____ e. Date of completion: _____ **III.** a. Name of the Agency: _____ b. Address of Work & Location :_____ c. Date of award of work: _____ d. Value of Work done: Rs._____ e. Date of completion: _____
Please Note-1. The copy of experience certificate/work order should be from the agency/agencies for which the tenderer has successfully completed similar nature of works in any Office Building of Government/PSU/Private organizations of repute i.e. self-attested copy of work order/completion certificate must be enclosed.(Self attested Copies of the above shall be enclosed).	

Signature and seal of tenderer
Name
Capacity /authority to sign
Full address:

The Cotton Corporation of India Limited

भारतीय कपास निगम लिमिटेड

(भारत सरकार का उपक्रम(वस्त्र् मंत्रालय के अंतर्गत् ,

निगमित पह्चान संख्या :U51490MH1970GOI14733

सी सी आय वेयर हाऊसिंग कॉम्प्लेक्स ,5 एस.प्लाट नं,सेक्टर –के डब्लू सी) 410218 -नवी मुंबई ,कलंबोली ,महाराष्ट्र राज्य(

दूरभाष्/PHONE/फैक्स/FAX:022-27420436/27424191 बेब साईट/website : www.cotcorp.org.in

ई/मेल-E-mail:kalamboli@cotcorp.com

प्रशासकीय एवं पंजीकृत कार्यालयकपास भवन प्लॉट नं.3:ए सेक्टर -,10सीबीडी बेलापुर(महाराष्ट्र राज्य)400614 – नवी मुंबई ,

दूरभाष् /PHONE:27579217 ०ग्राम/GRAM:COTCORPIND ०फैक्स/FAX:(022)27576030-9219-6069

ई/मेल-E-mail:headoffice@cotcorp.com वस्त्र् मंत्रालय बेब साईट /Ministry of Textiles website : www.ministryoftextiles.gov.in

TENDER DOCUMENT FOR

Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218

FINANCIAL BID-II

INDEX

Sr.No.	Particulars	Page No.
1	BILL OF QUANTITY	1-3

The Cotton Corporation of India Limited

भारतीय कपास निगम लिमिटेड

(भारत सरकार का उपक्रम(वस्त्र् मंत्रालय के अंतर्गत् ,

निगमित पहचान संख्या :U51490MH1970GOI14733

सी सी आय वेयर हाऊसिंग कॉम्प्लेक्स ,5 एस.प्लाट नं,सेक्टर –के डब्लू सी) 410218 -नवी मुंबई ,कलंबोली ,महाराष्ट्र राज्य(

दूरभाष्/PHONE/फैक्स/FAX:022-27420436/27424191 बेब साईट/website : www.cotcorp.org.in

ई/मेल-E-mail:kalamboli@cotcorp.com

प्रशासकीय एवं पंजीकृत कार्यालयकपास भवन प्लॉट नं.3:ए सेक्टर -,10सीबीडी बेलापुर(महाराष्ट्र राज्य)400614 – नवी मुंबई ,

दूरभाष् /PHONE:27579217 ∘ग्राम/GRAM:COTCORPIND ∘फैक्स/FAX:(022)27576030-9219-6069

ई/मेल-E-mail:headoffice@cotcorp.com वस्त्र् मंत्रालय बेब साईट /Ministry of Textiles website : www.ministryoftextiles.gov.in

Date: _____

FINANCIAL BID- II

To,
The Cotton Corporation of India Ltd.,
CCI Warehousing Complex, Plot No. s-5,
Sector-KWC, Kalamboli,
Navi Mumbai – 410218

Sub: **Re -Tender for Repairing, testing & commissioning of firefighting System installed at the CCI Warehousing Complex, Plot No. S-5, Sector KWC, Kalamboli, Navi Mumbai – 410218**

Sir,

With reference to your re-tender notice dated 05.03.2020 I/we are submitting my/our Financial Bid for the following work as below:-

Sr. No.	Description	Qty.	Units	Rate	Amount (in Rs.) Excl. Taxes
1	Refurbishing and revisioning of Main Electrical sprinkler system Motor Kirloskar make 65HP (Pump Room No. 1) with Motor driven pump Kirloskar make model no. DB 100/26 on replaceing of Pump Gland Pusher, sleeve, rewinding, Painting of motor and pump, Gasket set, Supporting stand shaft, Gland rope, Terminal connection box, Bearing set DE/NDE on motor and pump, motor REWINDING, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	Set		
2	Refurbishing and revisioning of Jocky Electrical sprinkler system Motor Kirloskar make 15HP (Pump Room No. 1) with Motor driven pump Kirloskar make model no. CPHM 25/26 on replaceing of Pump Gland Pusher, rewinding, Painting of motor and pump, sleeve, Gasket set, Supporting stand shaft, Gland rope, Terminal connection box, Bearing set DE/NDE on motor and pump, motor REWINDING, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	Set		
3	Refurbishing and revisioning of DIESEL DRIVEN PUMP Kirloskar make model no. DB 100/40 (Pump Room No. 1) on replacing of Pump Gland Pusher, sleeve, Gasket set, Gland rope, Terminal connection box, Bearing set DE/NDE, Painting of pump, key set, water deflector, Coupling rubber spider with servicing charges etc. complete as required.	1	No.		

4	Refurbishing and revisioning of DIESEL Engine Kirloskar make model no. RB-66 (Pump Room No. 1) on replacing of Engine spares oil 20 Ltr, oil filter element, Fuel filter kit 1.1 ltr, sleeve for nozzle holder, nozzle leak off pipe, leak off pipe connecter, Fuel pipe plastic braided, hose connecting water outlet, worm drive hose clips-2, hose 38x54, worm drive hose clips -10, Hose, Hose clips 32x48, Hose clips 28x30, Flexible cables, set of joints and rubber o ring set, set of copper washers set, V-belt, set of joints RB 66 and diaphragm, repairing and service of starter and Alternator with servicing charges etc. complete as required.	1	No.		
5	Supply of new 12 Volts, 1800 MHD Exide make battery with 150 Sq. mm. copper single core cable with copper lugs etc. Complete as required.	6	No.		
6	Modification of starter panel in pump room no. 1 of Main Electrical sprinkler system Motor 65HP, Jocky Electrical sprinkler system Motor 15 HP and battery charging panel on Diesel engine set RB-66 on replacing of 0-500Volt voltmeters, RYB indication lamps, on/off/trip indication lamps, on/off push buttons, all control functions including automatic starting of engine and trickle charging of batteries, over load relay, reset chord push button, control fuse, HC fuses with servicing charges etc. complete as required.	1	Set		
7	Refurbishing and revisioning of Jocky Electrical sprinkler system Motor Crompton Greaves make 15KW/20HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. DB 32/26 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, water deflector, Coupling L150 with servicing charges etc. complete as required.	1	Set		
8	Refurbishing and revisioning of Main Electrical sprinkler system Motor Crompton Greaves make 90KW/120HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. 6UP4 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	Set		
9	Refurbishing and revisioning of DIESEL Engine Greaves Ltd make model no. 4-YDC/126 BHP (Pump Room No. 2) on replacing of Engine spares Greaves maxtherm 15w40 oil 50 Ltr, oil filter element, Fuel filter kit 1.1 ltr, Fuel Micro filter kit 1.1Ltr, Instakool coolant 5 ltrs 2 pack, set of hoses, set of hose clamps, cleaning of diesel fuel tank, diesel fuel tank level gauge, Fuel Flexible GK-056 pipe 3 ft, Fuel Flexible GK-019 pipe 3 ft, Banjo bolts set, copper washer set, repairing and service of starter and Alternator with servicing charges etc. complete as required.	2	Nos.		
10	Refurbishing and revisioning of DIESEL DRIVEN sprinkler PUMP Kirloskar make model no. CPHM 125/40 with 70KC2-100HP (Pump Room No. 2) on replacing of Pump Gland Pusher, Shaft sleeve, Gasket set, Gland rope, Bearing set DE/NDE, Painting of pump, key set, coupling rubber star with servicing charges etc. complete as required.	1	No.		
11	Refurbishing and revisioning of DIESEL DRIVEN Hydrant PUMP Kirloskar make model no. 6UP4 (Pump Room No. 2) on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	No.		

12	Refurbishing and revisioning of Main Electrical Hydrant system Motor Crompton Greaves make 75KW/100HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. 6UP4 on replaceing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Gland rope, cooling pipe, Key set, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling rubber star with servicing charges etc. complete as required.	1	Set		
13	Refurbishing and revisioning of Jocky Electrical Hydrant system Motor Crompton Greaves make 15KW/20HP (Pump Room No. 2) with Motor driven pump Kirloskar make model no. DB 32/26 on replacing of Pump Gland Pusher, shaft sleeve, Painting of motor and pump, Gasket set, Key set, Gland rope, Bearing set DE/NDE on pump, motor winding varnishing, cooling pipe, water deflector, Coupling L150 with servicing charges etc. complete as required.	1	No.		
14	Servicing and reconditioning of MCCB control panel in pump room no. 2 and DIESEL Engine Greaves Ltd make on replacing of 0-500Volt voltmeters, control fuse link, NS type connectors, Indication lamps, on/off/trip indication lamps, on/off push buttons, Heater, contactor, all control functions including automatic starting of engine and trickle charging of batteries, over load relay, with servicing charges etc. complete as required.	1	Set		
15	Refurbishing and revisioning of valve inside connected on sprinkler and Hydrant line in pump room no. 1 & 2	1	Lot		
16	Supply of new 80 mm CI Foot Valve kirloskar make with installation complete as required.	2	No.		
17	Supply of new 200 mm CI Foot Valve kirloskar make with installation complete as required.	4	No.		
Total					

Total Value (in Rupees_____)

1. The rates are exclusive of all taxes as applicable and inclusive of all material, transportation, labour, tools, testing, etc. complete.
2. The work shall be completed within 21 days from the date of issue of work order.
3. The site shall be cleaned after completion of work
4. L-1 will be decided on the basis of Total value.
5. This offer valid for 60 (Sixty) days from the Bid Due Date specified in the Tender Form.
6. In witness thereof, I/ we submit this Financial Bid under and in accordance with the terms of the Tender Form document.
7. I/ We agree and understand that the Financial Bid is subject to the provisions of the Tender Documents. In no case, I/ we shall have any claim or right of whatsoever nature if the Scope of Work is not awarded to me/ us or my/ our Financial Bid is not opened or rejected.
8. I/ We shall make available to the Corporation any additional information it may find necessary or require to supplement or authenticate the Financial Bid.
9. I/ We acknowledge the right of the Corporation to reject my/ our Financial Bid without assigning any reason or otherwise and hereby waive, to the fullest extent permitted by applicable law, my/ our right to challenge the same on any account whatsoever.
10. In witness thereof, I/ we submit this Financial Bid under and in accordance with the terms of the Tender Form document.

Signature and seal of tenderer

Name

Capacity /authority to sign

Full address: