भा.क.नि

CCI

भारतीय कपास निगम लिमिटेड

THE COTTON CORPORATION OF INDIA LIMITED

(भारत सरकार का उपक्रम)

कपास भवन: एस. सी. ओ. 7-11,न्यू हाउसिंग बोर्ड,बरनाला रोड,सिरसा-125055

Kapas Bhawan : S.C.O. 7 to 11, New Housing Board, Barnala Road, Sirsa(Hr.) 125055

दूरभाष : 01666-248601, 248602, 248605 फैक्स : (01666) 248604

Website:www.cotcorp.org.in Email:sirsa@cotcorp.com MinistWebsite:www.texmin.gov.in

संख्या: भाकनि/ हरि./ जि॰&पी॰/2018-19/ दिनांक 29-06-2018

निविदा सूचना

भारतीय कपास निगम लिमिटेड सिरसा फसल वर्ष 2018-19 के लिए प्रस्तावित निम्न केन्द्रों पर जिनिंग एवं प्रेसिंग कार्य हेतु प्रतिष्ठित जिनिंग एवं प्रेसिंग फैक्ट्रियों से 2 बिड तकनीक (टेक्निकल बिड-1 तथा फाइनेंसियल बिड-2) के अंतर्गत मुहरबंद निविदाएँ आमंत्रित करता है:-

सिरसा, कालांवाली, एलनाबाद, डबवाली, फतेहाबाद, आदमपुर, हिसार, जींद, उकलाना, भुना, भट्टू, उचाना, बरवाला |

निविदाकर्ता यह सुनिश्चित करें कि उनके पास उपयुक्त प्राधिकारी द्वारा जारी भविष्यनिधि कोड नंबर (Provident Fund Code No.) एवम GST नंबर है।

निर्धारित निविदा फार्म नियम एवं शर्तों सहित शाखा कार्यालय से किसी भी कार्य दिवस में कार्यालयीन समय में रु॰112/- (रुपए एक सौ बारह मात्र) GST सहित, का भुगतान बैंक ड्राफ्ट या पे-ऑर्डर द्वारा कर दिनांक 13.07.2018 तक प्राप्त किया जा सकता हैं। निगम की वेबसाइट http://www.cotcorp.org.in तथा सरकारी वेबसाइट http://www.eprocure.gov.in से भी निविदा डाउनलोड की जा सकती है। यदि वेबसाइट से निविदा फार्म डाउनलोड किया जाता है तो निविदा फार्म की टेक्निकल बिड के साथ रु॰112/- का बैंक ड्राफ्ट या पे-ऑर्डर जो कि भारतीय कपास निगम लिमिटेड, सिरसा के नाम पर देय हो, साथ में संलग्न करना अनिवार्य होगा। जो जिनिंग प्रेसिंग फैक्ट्रियाँ MSME के अंतर्गत आती हैं एवं MSME प्राधिकरण से पंजीकृत हैं वे वैध पंजीकरण प्रमाण पत्र प्रस्तुत करने पर निविदा शुल्क से मुक्त होंगी।

निविदाकर्ता निम्नानुसार निविदा प्रस्तुत करें:

1. **लिफाफा ए**- लिफ़ाफ़ा ए पर "**टेक्निकल बिड**" (Technical Bid) लिखा होना चाहिए जिसमें टेक्निकल बिड (Annexure-II) तथा साथ में संलग्न होने वाले सभी दस्तावेज़ होने चाहिए।
2. **लिफाफा बी**- लिफाफा बी पर "**फाइनेंशियल बिड**" (Financial Bid) लिखा होना चाहिए जिसमें फाइनेंशियल बिड (Annexure-III) हो।
3. **लिफाफा सी**- लिफाफा सी में उपरोक्त दोनों लिफाफे **ए** एवं **बी** डालें व सीलबंद कर शाखा कार्यालय सिरसा को भेजें।

प्रत्येक पूर्ण रूप से भरी हुई निविदा सीलबंद लिफाफे में जिसके ऊपर **"जिनिंग एवं प्रेसिंग निविदा 2018-19"** व नीचे केंद्र का नाम, निविदाकर्ता का नाम व पता स्पष्ट रूप से अंकित होनी चाहिए।

पूर्ण रूप से भरा निविदा आवेदन शाखा प्रबन्धक को संबोधित करते हुए शाखा कार्यालय सिरसा के उपरोक्त दर्शाये गए पते पर दिनांक 16.07.2018 को दोपहर 13:00 तक पहुंचाना आवश्यक है। निर्धारित समय में प्राप्त हुई मुहरबंद निविदाओं की सर्वप्रथम टेक्निकल बिड (Technical Bid) उसी दिन दिनांक 16.07.2018 को दोपहर 15:00 बजे उपस्थित निविदाकर्ताओं के समक्ष खोली जाएगी। टेक्निकल बिड (Technical Bid) में सफल निविदाकर्ताओं की फैक्ट्री सर्वे के उपरांत जिन निविदाकर्ताओं की फैक्ट्री टेक्निकल बिड (Technical Bid) के अनुसार योग्य पायी जाएगी उन निविदाकर्ताओं की ही फाइनेंशियल बिड (Financial Bid) दिनांक 24.07.2018 को दोपहर 15:00 बजे उपस्थित निविदाकर्ताओं के समक्ष खोली जाएगी। निगम किसी भी निविदा को पूर्ण अथवा आंशिक रूप से स्वीकार/ अस्वीकार करने का अधिकार अपने पास सुरक्षित रखता है।

शाखा प्रबन्धक

(TECHNICAL BID)

(Annexure II)

(TO BE SUBMITTED ON LETTERHEAD OF G&P FACTORY)

Tender for Job Work of Ginning & Pressing for Cotton Season_2018-19

(Technical Bid)

Tender Form: _____ Tender form fees: 112/-(including GST)

Date of issue : _____

PART-I

1. Name of the center : _____

2. Full Name of the factory, Address with Pin code, Telephone/Mobile/ Fax Numbers E Mail (If any) _____ _____ _____ _____

3. Whether Factory is MSE or not : (Please tick (✓) whichever is applicable and if Yes, attach valid certificate and UAM No. is mandatory) Yes No

   UAM No. : _____

4. If MSME whether under SC/ ST category : (if Yes, Pls. attach concerned valid certificate Yes No

5. Category of Ginning & Pressing factory (Please tick (✓) whichever is applicable)

   i) Modernized composite ginning & pressing factory through TMC assistance and certified by Textile Committee.

Please tick (✓) Star Rating	I	II	III	IV	V

   ii) Modernized composite ginning & pressing factory other than TMC assistance and certified by Textile Committee.

Please tick (✓) Star Rating	I	II	III	IV	V

   iii) Modernized composite ginning & pressing factory through TMC assistance.

   iv) Modernized composite ginning & pressing factory other than TMC assistance.

   v) Non- Modern ginning & pressing factory.

5. Constitution – Company / Partnership / Sole Proprietary _____

6. Name of the Directors/partners and their occupation.
   1. _____
   2. _____
   3. _____

7. Name and address of the sister concern, if any. _____ _____

8. Name of Proprietor or Active Partner. _____

9. Name of Factory Manager/Other Responsible person, along with Tel. No. _____

10. P.F. Code No.
(Please attach certificate issued by Regional Provident Fund Commissioner) _____

11. PAN from Income Tax Department (Attach Copy) _____

12. Whether factory has sufficient Managerial, Supervisory & Technical staff — Yes / No

13. Details of processing of bales during last three years

	2015-16	2016-17	2017-18
i) For CCI	---------	---------	---------
ii) Own	---------	---------	---------
iii) Other parties	---------	---------	---------

14. Details of processing capacity of factory and to be offered to CCI

Type	Machines		Production of bales of allotted capacity		Exclusive/ Turn basis*
	Total	Offered to CCI	Per week	Per month	(Days in a week)
Saws set					
Double Rollers					
Single Rollers					
Pressing					

If Turn basis then number of bales of CCI stock which will be processed per month

15. Details of Fire Accidents in the Factory for the Last three Years :

S. N.	PARTICULARS	YEAR 2015 -16		YEAR 2016-17		YEAR 2017-18	
		NO.	LOSS	NO.	LOSS	NO.	LOSS
(i)	Fire Accidents in Open Compound						
(ii)	Fire Accidents in Gin. House						
(iii)	Fire Accidents in Press House						
(iv)	Fire Accidents in Godown/Barrack						

16. Details of heap platforms/sheds/barracks/pal a house/godowns available in factory and to be offered to CCI free of cost

	Availability		Allotment to CCI	
	No.	Capacity	No.	Capacity
Heap Platforms				
Sheds				
Barracks				
Pallahouse				
Godowns				

17. Classification of the factory as per Insurance tariff rules. _____

18. GST registration Number (Attach GST registration Copy) _____

19. Banking Details for Net Banking/ RTGS/ NEFT Details:

Name of the Account Holder	
Name of Bank	
Bank Account Number	
IFSC Code	

PART-II

MINIMUM STANDARDS REQUIRED FOR ENGAGEMENT OF G & P FACTORY

S.No	Item	Minimum Requirements	Availability in G&P Factory
1	**Ginning Machines**	12 DRs of normal size / 11 extra-long DRs/ 9 Jumbo DRs with Auto feeder/ 1 or 2 saw gins with equivalent processing capacity of 3-4 bales per hour.	
2	**Pre cleaner**	Cleaner with capacity to suit the processing speed of the ginning machines.	
3	**Lint Cleaner**	Cleaner with capacity to suit the processing speed of ginning machines.	
4	**Kapas Conveyor System**	(i) Pneumatic conveyor with Stone Catcher for the first stage from heaps to Precleaner; (ii) Mechanical/ Pneumatic conveyor from Precleaner to individual gins. Central Platform system not permitted unless it exists already.	
5	**Lint Conveyor System**	Mechanical / Pneumatic Conveyor (i) from Gins to Lint Cleaner; (ii) from Lint Cleaner to each Pala Hall and (iii) from each Pala Hall to a. Bale Press Hall in case of existing Conventional Bale Press b. Bale Press box through Lint slide & Pusher Mechanisms in case of modern Bale Press (direct feeding of cotton from Lint Cleaner to Press box permitted)	
6	**Bale Press**	Single stage oil hydraulic, auto tramping Bale Press with Lint Slide and Pusher mechanism for direct feeding of lint into the press box. Conventional water hydraulic, two-stage presses without auto tramping facility will, however, be permitted if they already exist.	
7	**Conveyor for Seed**	Automatic Conveyor from gins to Seed Platform	
8	**Humidifier/ Moisturizer**	In Gin Hall In case of Central Platform, **2 Benson fans or adequate number of nozzles.** **In Pala Halls** 2 Benson fans in each Hall or adequate number of nozzles.	

9	**Fire Fighting System**	Overhead tank/ sump (capacity 65,000 liters), with a minimum of 6 hydrants strategically located, hose pipes with nozzles and a stand-by diesel pump besides an electric pump.	
10	**Underground Wiring**	All high tension and low tension wires/cables to be under-ground	
11	**Weigh Bridge**	Capacity: 20 tons/ 5 tons depending on local needs (Not required if the facility is available nearby)	
12	**Pucca Platform for Kapas**	Raised platform with a minimum of 5,000 sq. ft. area.	
13	**Covered Storage Space for Lint (Pala Halls)**	Hall(s) with a minimum area of 2000 sq. ft., pucca floor.	
14	**Seed Platform**	Raised, platform of minimum 1000 sq. ft. area.	
15	**Bale Storage Space**	Platform with cemented floor adjoining Press Hall and admeasuring a minimum area of 600 sq. ft.	
16	**Road**	CC Road with at least 10 ft. width.	
17	**Boundary Wall/ Fence**	Wires mesh fence or barbed wire fence with less than 1 ft. gap between wires, or masonry wall, all of a minimum height of 6 ft.	
18	**CCTV cameras in G & P Factory at given locations**	Location of CCTV Camera in G & P Factory:- 1. Factory Weighbridge 2. Path from Weigh Bridge to Factory entry gate. 3. Entry Gate. 4. Kapas Platform. 5. Gin Hall. 6. Press Hall 7. Exit gate.	

PART-III

Scope of Works :-

All work commencing from unloading of kapas for processing in the factory to loading of F.P bales for dispatching to CCI hired Godowns including sample cutting i.e. 2 samples to be drawn from each lot of 100 bales. The detail of the work to be carried out in the factory is as under:

For Ginning:	**For Pressing:**
Providing of required number of labourers for all stages of work beginning from unloading of kapas up to gin house and inter-alia the following stages of work in the course of ginning: i) Unloading of kapas received from mandi to heaping of kapas (including all work related to tangliwala, cleaning and grading of heap & its surroundings, picking of nearby scattered kapas etc.). ii) In case, kapas weighment is done in factory, then unloading of palli from palli kanta / weighing scale (including tying of palli) to heaping of kapas (including all work related to tangliwala, cleaning and grading of heap & its surroundings, picking of nearby scattered kapas etc.). iii) All work related to jaffri (including grading, cleaning & chugai, picking of foreign partilces, khokhri, yellow pickings, and other contaminants and misc. etc. from heaps). iv) Carrying of graded kapas from the grading hall/heap to gin hall. v) Feeding of kapas to the gins. vi) Cleaning of lint, filling into the lint boras, weighment of lint boras if any, and stacking of boras. vii) Picking of roll touch and yellow picking from the lint at the time of ginning. viii) Transportation of lint to the press hall and in case of Ginning unit only – to Press Hall of pressing factory at the same centre or another centre. ix) Carrying of seeds from the gin hall to seed godown. x) Sweeping of lint in ginning hall, picking	Providing of required number of labourers for mixing as well as cleaning of lint before feeding in the opener and pressing of bales with standard weight of 170 kg net lint with tolerance limit of +/- 5 kgs for all months except during March to June when the tolerance shall be of +/- 7 Kgs. ,fully covered with new iron hoops(18/19 gauge, 1/2" width) / polyester strappings (width 19.05 mm, thickness 1.02 mm , conforming to type II of IS 15559:2004, colour green) to be arranged by the factory and with 100% cotton cloth (20X20 count, 48X40 R&P, 127 cm width, weight 122 gms per Sq.Metres) to be arranged by corporation/ G&P factory, with stitching and covering of bales from all sides including top and bottom, besides handling of lint stocks beginning from opening of lint boras/boundaries till loading of bales for dispatching in godowns after marka and weighment and inter-alia the following stages of work in the course of pressing of lint into cotton bales: i) Unloading, carrying and stacking of the lint boras from within the factory or to be received from outside. ii) Carrying and opening of lint in the lint hall. iii) Picking of sutli from lint boras and cleaning of boras by picking of lint from boras completely. iv) Pala making v) Feeding of cleaned lint into the press box. vi) Removing of bales from press platforms to stacking point. vii) Weighment of bales/ rechecking of weight by CCI officials. viii) Marking of bales. ix) Sample cutting (2 each per lot of 100

of kapas boras from heap to gin hall and removing gin waste and miscellaneous items etc. to storing points. xi) All work related to Cotton seed including removal of cotton seed from near the berm to provide sufficient space for storage of seed, collection and cleaning of scattered cotton seed and cleaning of cotton seed from khokhri. xii) Weighment of lint if required. xiii) Loading & Unloading of Corporation's miscellaneous stock such as tarpaulin, pallis, grey cloth etc. in factory. xiv) Maintenance of tarpaulins, pallies, grey cloth etc. of Corporation. Covering & uncovering of kapas, bales & cotton seed of CCI with tarpaulins on regular basis. Also, at the end of the season handing over all the tarpaulins & pallis to the Centre Incharge of CCI. xv) Any extra labour required to be deployed in the case of ginning of kapas and in emergencies and natural calamities like rain, lightening, thunder, cyclone etc.	bales). x) Loading of bales in vehicles from press platform for storage of bales in godowns. xi) Any extra labour required to be deployed in the course of pressing of bales and in emergencies and natural calamities like rain, lightening, thunder, cyclone etc.

If situation requires on need basis the following works has to be done:

Filling, Stacking, De-stacking, Weighment of Cowdy / Ginjump, Empty lint bora restichting, Re-heaping of kapas heap, Re-heaping of cotton seed heap, Turning over of Cotton bales, coverage of Kapas, seed, bales by tarpaulins.

I/We have gone through the detailed terms and conditions for hiring of G&P factories by the Corporation and agree to carry out the complete processing work as per standards and requirements of the Corporation.

Signature

Name of the Authorized Signatory

Address of the factory with seal

Date:

(FINANCIAL BID) (Annexure III)

(TO BE SUBMITTED ON LETTERHEAD OF G&P FACTORY)

(Financial Bid)

S.No.	Particulars	Processing Type	
		Roller	**Sawgin**
1	Combined ginning & pressing rates per bale with iron hoops **without including cost of cloth**	Rs._____	Rs._____
2	Combined ginning & pressing rates per bale with iron hoops including cost of cloth	Rs._____	Rs._____
3	Ginning rate per quintal of lint	Rs._____	Rs._____
4	Pressing rate per bale with iron hoops and with cost of 100% cotton cloth.	Rs._____	Rs._____
5	Combined ginning & pressing rates per bale with Polyester strappings including cost of cloth	Rs._____	Rs._____
6	Pressing rate per bale with polyester strappings and with cost of 100% cotton cloth.	Rs._____	Rs._____
7	Pressing rate per bale without iron hoops /polyester strappings and with cost of 100% cotton cloth.	Rs._____	Rs._____
8	Pressing rate per bale without iron hoops/polyester strappings and without including cost of cloth.	Rs._____	Rs._____
Note	**Above rates should be quoted for 9 Gallas. In case of 10 Gallas, Rs. 7/- per bale and in case of 12 Gallas Rs. 12/- per bale will be added to Combined Ginning & Pressing Rates**		

The above quoted rates are inclusive of all work commencing from unloading of kapas for processing in the factory to loading of FP bales for dispatching to CCI hired godowns, including sample cutting (2 samples to be drawn from each lot of 100 bales). Detailed scope of work is as mentioned under point 1 of Part III of technical bid.

Note:

- Incentive of Rs. 2/- per bale for Modern factories with 4 to 5 Star Rating by Textile Committee
- Incentive of Rs. 1/- per bale for Modern factories with 2 to 3 Star Rating by Textile Committee
- The specifications for iron hoops (18/19 gauge, 1/2" width) , polyester strappings (width 19.05 mm, thickness 1.02 mm , conforming to type II of IS 15559:2004, colour green) and specification of 100% cotton cloth (20X20 count, 48X40 R&P, 127 cm width, weight 122 gms per Sq. meters) should be considered while quoting above rates.
- Please strike out whichever is not applicable.
- The above rates are inclusive of all expenses, taxes and levies if any by Central / State Government and Local Authorities but exclusive of GST.
- TDS and surcharge as per Income Tax Act shall be deducted by the Corporation.

Specific rates must be quoted clearly. Tenders without quoting specific rates or with indications of negotiations on CCI rates/as per CCI rates/Government rates etc. will be rejected.

I/We have gone through the detailed terms and conditions for hiring of G&P factories by the Corporation and agree to carry out the complete processing work as per standards and requirements of the Corporation.

Signature
Name of the Authorized Signatory
Address of the factory with seal

Date:

भा.क.नि

CCI

भारतीय कपास निगम लिमिटेड

THE COTTON CORPORATION OF INDIA LIMITED

(भारत सरकार का उपक्रम)

कपास भवन: एस. सी. ओ. 7-11,न्यू हाउसिंग बोर्ड,बरनाला रोड,सिरसा-125055

Kapas Bhawan : S.C.O. 7 to 11, New Housing Board, Barnala Road, Sirsa(Hry.) 125055

दूरभाष : 01666-248601, 248602, 248605 फैक्स : (01666) 248604

Website:www.cotcorp.org.in Email:sirsa@cotcorp.com MinistWebsite:www.texmin.gov.in

Tender for Job Work of Ginning & Pressing for Cotton Season 2018-19

TERMS AND CONDITIONS

i) The tender form duly filled in, in all respects and signed by the Authorized Signatory, should be submitted in a sealed cover super scribed as "Ginning and Pressing tender for cotton season **"2018-19"** within the stipulated time and date. Tender forms received after the stipulated time and date will not be considered.

ii) All columns in the tender form should be filled in clearly and legibly. Tender form found as incomplete in any respect, may be rejected at the discretion of the Corporation.

iii) Mere submission of the tender form does not entitle any factory to be engaged by the Corporation.

iv) L1 factory shall be considered for hiring provided it meets the minimum standards required as per the tender terms. When more processing facility is required at the center then on need basis the L2/L3/L4 & so on factory could be engaged provided they agree at the rates of L1.
G & P Rates being the same, the Corporation will consider hiring of ginning and pressing factories in the following order of preference:

(a) Modernized composite ginning & pressing factory through TMC assistance and certified by Textile Committee.
(b) Modernized composite ginning & pressing factory other than TMC assistance and certified by Textile Committee.
(c) Modernized composite ginning & pressing factory through TMC assistance.
(d) Modernized composite ginning & pressing factory other than TMC assistance.
(e) Composite G&P factories in MSEs / Co-operative sector / other institutions.
(f) Composite G&P factories with track record of good performance.
(g) G&P factories willing to give their full capacity on exclusive basis to CCI.

Note:

1. Online Modern Factories, Factories having power supply through express feeder and the Factories having diesel generator sets shall have added advantage.
2. G& P Factories must obtain fire safety certificate from the concerned Authorities of Haryana Govt.

v) In the event of Corporation finalizing to hire the ginning and pressing factory, the concerned factory will have to enter into an agreement with the Corporation in the prescribed form with acceptance of all its terms and conditions. The factory will also submit a copy of partnership deed/ memorandum of article/ memorandum of association as the case may be.

vi) In case the L1 tenderer refuse to work at the rates quoted by him, such factories shall not be awarded any work for at least one year i.e. next cotton season.

vii) All the pages of the Tender Form as well the Terms & Conditions should be signed by the factory owner.

viii) In case, Bidder has any query about the bidding conditions and/or bidding process - may seek comments from the Branch Office. Further in case, if any bid is rejected or a tender document is not issued to prospective Bidder - may seek the reasons for rejection from Branch Office.

DECLARATION

I/We hereby confirm that the above clauses have been read and noted and we agree to abide by all the above Terms and Conditions.

Signature

Name of the Authorized Signatory

Address of the factory with seal

Date:

DEDUCTIONS FOR NON -AVAILABILITY OF FOLLOWING INFRASTRUCTURE

ANNEXURE-"A"

SL. NO.	PARTICULARS	DEDUCTIONS PER BALE (IN RS.)
01	BOUNDARY WALL/ WIRE FENCING	**20-00**
02	PAKKA CEMENTED 1 Ft. RAISED HEAP PLAT FORM FOR MINIMUM 1(GINNING CAPACITY(up to 12 GINGS MIN 400 BLS CAPACITY FROM 13 TO 500 BLS CAPACITY FROM 18 & ABOVE 800 BLS CAPACITY)	**30-00**
03	COTTON SEED STORAGE 1 Ft. RAISED CEMENTED PAKKA PLAT FORM	**20-00**
04	PAKKA PLAT FORM FOR BOUNDARY /FP. BALES 100 EACH	**20-00**
05	TROLLYS TO CARRY LINT BORAS	**10-00**
06	COTTON SEED CONVEYOR WITH ELIVATOR SYSTEM	**30-00**
07	KAPAS CLEANER	**30-00**
08	LINT OPENER	**50-00**
09	BALE TOP & BOTTOM TO BE INSERTED IN PATTIES/IMPROPER PACKING BALES	**50-00**
10	WATER HYDRANTS SYSTEM FOR FIRE FIGHTING	**50-00**

WE AGREE WITH THE G&P RATES DECIDED ON _____ SUBJECT TO ABOVE DEDUCTIONS.

SIGNATURE OF THE AUTHORISED SIGNATORY
(WITH SEAL)